

## वसंतराव नाईक राज्य कृषी विस्तार व्यवस्थापन प्रशिक्षण संस्था व्ही.आय.पी. रोड, धरमपेठ, नागपूर -४४००१०



E Mailsameti123@yahoo.co .in	Phone- 0712 2555999, 2541944			
प्रति,	जा. क्रं. वनामती/ बांधकाम/ <sup>553</sup> /२०२४ नागपूर दि . १९१७३/२०२४			

विषय- वनामती परिसरातील समिती सभागृहामधील विविध नुतनीकरण कामे करणेकरिता दरपत्रके मागविण्याबाबत.

उपरोक्त विषयानुसार वनामती परिसरातील समिती सभागृहामधील विविध नुतनीकरण कामें करावयाची आहे.

सदर दरपत्रक सुचना प्राप्त होताच संस्थेत प्रत्यक्ष भेट देऊन कामाची पाहणी करून सोबत जोडलेल्या प्रपत्रनिहाय कामाची दरपत्रक कार्यालयास मा. संचालक, वनामती नागपूर या नावाने दिनांक २७ .०३.२०२४ रोजी कार्यालयीन वेळेपर्यंत सादर करावे.

वरिष्ठ प्रसामित नि लेखा अधिकारी वसंतराव नाईक राज्य कृषि विस्तार व्यवस्थापन प्रशिक्षण संस्था, नागपूर.

प्रत-

- १. कार्यालयीन नोटीस बोर्ड
- २. वनामती कार्यालयाची वेबसाईट www.vanamati.in

Sr no	Particulars of work	Qty	Unit	Rate	Amount
1	Conference Table Modification	1	Job		
	Renovation of existing conference table with 6mm				
	plywood on table top surface finished with laminates				
	and front facia 4 mm veneer with polishing as per the				
	design etc complete				·
2	Providing and fixing 75mm thick partition made out of	4.8	sqmt		
	18mm plywood on surface finished with decorative				
	charcoal sheet inserts and laminates from both sides.				
3	Providing and fixing sound proof entrance door with	1	No.		
	sandwich panels surface finished with laminates of				
	selected colours, covering entire front facade etc				
J	complete including all door fitting like handle hinges				-
	tower bolt , aldrop latches ,either floor spring /door				
	closure etc complete.				
4	Decorative panneling on sceen wall (5x3.0 m)	15	Sq.m.		
	Providing and fixing wall panelling with 18mm plywood				
	screw fixed to Aluminium sq pipe frame, surface				
	finished with veneer and polishing the same with				
•	charcoal sheet inserts.				
5	Pannelling on 2 No. longer wallsProviding and fixing	62.4	Sq.m.		
	wall panelling with 18mm plywood screw fixed to				
	Aluminium pipes at 2' c/c horizontally, surface finished				
	with Veneer polishing the same in combination with				
	techno panels as per the colour selected etc. complete.				
6	Texture paint on Director's side short wall	24	Sq.m.		
7	Providing and fixing roller fabric blinds to windows with	12	Sq.m.		
	100% light reduction with pelmet etc complete				
8	Breaking, repairs & painting of false ceiling	1	Job		
9	TOTAL				C
10	GST 18%		18%		C
11	Final Total	TOTAL (A)			