

वसंतराव नाईक राज्य कृषी विस्तार व्यवस्थापन प्रशिक्षण संस्था व्ही.आय.पी. रोड, धरमपेठ, नागपूर -४४००१०



E Mail -sameti123@yahoo.co .in

Phone- 0712 2555999, 2541944

जा. क्रं. वनामती/ बांधकाम/2 353 /२०२४ नागपूर दि . 22/07 | 2024 प्रति,

विषय- वनामती संस्थेच्या परिसरातील वनलता वासिगृहात ॲल्युमिनियमच्या खिडक्या बसविण्याबाबत दरपत्रके मागविण्याबाबत.

उपरोक्त विषयानुसार वनामती परिसरातील वनलता वसतिगृहातील पहिला ते पाचव्या मजल्यावरील Passage मधील उघड्या भागात मोठया आकाराच्या Aluminium Sliding Window लावायच्या आहेत.

सदर दरपत्रक सुचना प्राप्त होताच संस्थेत प्रत्यक्ष भेट देऊन कामाची पाहणी करून दरपत्रक कार्यालयास मा. संचालक, वनामती नागपूर या नावाने दिनांक २९.०७.२०२४ चे कार्यालयीन वेळेपुर्वी दरपत्रकासोबत पॅन कार्ड/जीएसटी/नोंदणी प्रमाणपत्राची झेरॉक्स प्रत जोडावी. उशिरा येणा-या दरपत्रकाचा विचार केला जाणार नाही, याची कृपया नोंद घ्यावी. कामाचे विवरणपत्र सोबत जोडले आहे.

सहपत्र-विवरणपत्र

वसंतराव नाईक राज्य कृषि विस्तार व्यवस्थापन प्रशिक्षण संस्था, नागपूर.

प्रत-

- १. कार्यालयीन नोटीस बोर्ड
- २. वनामती कार्यालयाची वेबसाईट www.vanamati.in

Name of Work- Providing and fixing Aluminium Window at VANALATA Hostel Passage, VANAMATI, Nagpur.

SCHEDULE -B

Sr No.	Particulars of Item	Approx. Qty	Rate/ per	Amount
1	Providing and fixing in position (as per ISI1868/1982) Aluminium Sliding Window of two tracks two panel glass with fix window Jindal make aluminium 27 mm domal series, Colour anodised section, 2 track outer frame 21487(66.5 mm X 50 mm X 1.5 mm thick)weight 1.329 kg/mtr, sliding sash 21490 (65 mm X27mmX1.5 mm thick)weight 0.851 kg/mtr, interlock 19453 (38.7 mmX 28.5 mmX 1.4 mm thick)weight 0.303 kg/mtr, fix w frame 20063 (63.50 mmX38.10 mm X1.41 mm thick) weight 0.818 kg/mtr, G-clip 19352 (19.0 mm X 17.3 mm thick) weight 0.096 kg/mtr, window hardware etta excellanza, locking system concealed lock, roller heavy duty double roller, epdm gasket, joint clit, Glazing 5 mm thick clear Glass (Saint Gobain). As per detailed drawings and as directed by Engineer/Architect in charge with all necessary aluminium section fixuters and fastening with all required screw and nuts etc. including repairing and remaking the existing area complete. (windows to be provided for First floor to Fifth floor)	102.666 sqm (1104.69 sft)		

I am ready to execute the above work as per Standard Specification of PWD and as per rates given by me.

Contractor