



वसंतराव नाईक राज्य कृषी विस्तार व्यवस्थापन प्रशिक्षण संस्था  
व्ही.आय.पी. रोड, धरमपेठ, नागपूर -४४००१०



E Mail -sameti123@yahoo.co.in

Phone- 0712 2555999, 2541944

जा. क्रं. वनामती/ बांधकाम/ 238/2028  
नागपूर दि. 26/10/2028

प्रति,

-----  
-----  
-----  
-----

विषय- वनामती परिसरातील समिती सभागृहामधील विविध नुतनीकरण कामे करणेकरिता  
दरपत्रके मागविण्याबाबत. (दुसरी वेळ)

उपरोक्त विषयानुसार वनामती परिसरातील समिती सभागृहामधील विविध नुतनीकरण कामे  
करावयाची आहे.

सदर दरपत्रक सुचना प्राप्त होताच संस्थेत प्रत्यक्ष भेट देऊन कामाची पाहणी करून सोबत  
जोडलेल्या प्रपत्रनिहाय दरपत्रक कार्यालयास मा. संचालक, वनामती नागपूर या नावाने दिनांक  
०५.०८.२०२४ रोजी कार्यालयीन वेळेपर्यंत सादर करावे. दरपत्रकासोबत पॅन कार्ड/जीएसटी/नोंदणी  
प्रमाणपत्राची झेरॉक्स प्रत जोडावी. उशिरा येणा-या दरपत्रकाचा विचार केला जाणार नाही, याची कृपया  
नोंद घ्यावी. कामाचे विवरणपत्र सोबत जोडले आहे.

सहपत्र-विवरणपत्र

  
अपर संचालक

वसंतराव नाईक राज्य कृषी विस्तार  
व्यवस्थापन प्रशिक्षण संस्था, नागपूर.

प्रत-

१. कार्यालयीन नोटीस बोर्ड
२. वनामती कार्यालयाची वेबसाईट www.vanamati.in

**Name of Work :- Various Repairs and Renovation of Committee Hall in  
Administrative Building, at VANAMATI, Nagpur.  
Schedule of Work**

Sr no	Particulars of work	Qty	Unit	Rate	Amount
1	Conference Table Modification	1	Job		
	Renovation of existing conference table with 6mm plywood on table top surface finished with laminates and front facia 4 mm veneer with polishing as per the design etc complete				
2	Providing and fixing 75mm thick partition made out of 18mm plywood on surface finished with decorative charcoal sheet inserts and laminates from both sides.	4.80	sqmt		
3	Providing and fixing sound proof entrance door with sandwich panels surface finished with laminates of selected colours, covering entire front facade etc complete including all door fitting like handle hinges tower bolt, aldrop latches, either floor spring /door closure etc complete.	1	No.		
4	<b>Decorative panneling on sceen wall (5x3.0 m)---</b> Providing and fixing wall panelling with 18mm plywood screw fixed to Aluminium sq pipe frame, surface finished with veneer and polishing the same with charcoal sheet inserts.	15.00	Sq.m.		
5	Pannelling on 2 No. longer walls --Providing and fixing wall panelling with 18mm plywood screw fixed to Aluminium pipes at 2' c/c horizontally, surface finished with Veneer polishing the same in combination with techno panels as per the colour selected etc. complete.	62.40	Sq.m.		
6	Texture paint on Director's side short wall	24.00	Sq.m.		
7	Providing and fixing roller fabric blinds to windows with 100% light reduction with pelmet etc complete.	12.00	Sq.m.		
8	Breaking, repairs & painting of false ceiling	1	Job		
9	<b>TOTAL</b>				
	GST @18%				
	<b>TOTAL Rs.</b>				

I am/we are ready to execute the above work as per above Standard Specifications and directives of Engineer/Architech incharge.

Contractor

  
 Civil Engineer  
 VANAMATI, Nagpur.