



वसंतराव नाईक राज्य कृषि विस्तार व्यवस्थापन प्रशिक्षण संस्था



व्ही.आय.पी. रोड, धरमपेठ, नागपूर -४४००१०

E Mail -sameti123@yahoo.co.in

Phone- 0712 2555999, 2541944

जा. क्रं. वनामती/ बांधकाम/३३५१/२०२४
नागपूर दि. २५/०७/२०२४

प्रति,

विषय- वनामती संस्थेच्या परिसरातील वर्षा वसतिगृह व प्रशासकीय भवनावर अग्निशमन पाण्याची टाकी बनविण्याबाबत दरपत्रके मागविण्याबाबत.

उपरोक्त विषयानुसार वनामती परिसरातील वर्षा वसतिगृहातील तिस-या मजल्यावर व प्रशासकीय भवनावरील पहिल्या मजल्यावर आरसीसी टाकी प्रत्येकी १०००० लि. क्षमतेची बांधावयाची आहे.

सदर दरपत्रक सुचना प्राप्त होताच संस्थेत प्रत्यक्ष भेट देऊन कामाची पाहणी करून दरपत्रक कार्यालयास मा. संचालक, वनामती नागपूर या नावाने दिनांक ३०.०७.२०२४ चे कार्यालयीन वेळेपूर्वी दरपत्रकासोबत पॅन कार्ड/जीएसटी/नोंदणी प्रमाणपत्राची झेरॉक्स प्रत जोडावी. उशिरा येणा-या दरपत्रकाचा विचार केला जाणार नाही, याची कृपया नोंद घ्यावी. कामाचे विवरणपत्र सोबत जोडले आहे.
सहपत्र-विवरणपत्र


अपर संचालक

वसंतराव नाईक राज्य कृषि विस्तार
व्यवस्थापन प्रशिक्षण संस्था, नागपूर.

प्रत-

१. कार्यालयीन नोटीस बोर्ड
२. वनामती कार्यालयाची वेबसाईट www.vanamati.in

**Name of Work:- Construction of Overhead Fire tank on First Floor Roof on Institute Building And
Third Floor Roof on Varsha Hostel at Vanamati, Nagpur**

SCHEDULE B

Item. No.	Particulars of item	Qty	Rate		Unit	Amount
			In Figures	In Words		
1	Providing and laying Cast in situ/Ready Mix cement concrete M-25 of trap / granite /quartzite/ gneiss metal for R.C.C. columns as per detailed designs and drawings or as directed including steel centering, formwork, cover blocks, laying/pumping, compaction finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening if special finish is to be provided and curing etc. complete.(Excluding reinforcement and structural steel).with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)					
	First Floor	0.50	16801.40	Rupees Sixteen Thousand Eight Hundred One & Forty Paise only.	M3	8346.90
	Third Floor	0.50	17080.75	Rupees Seventeen Thousand Eighty & Seventy Five Paise only	M3	8485.70
2	Providing and laying Cast in situ/Ready Mix cement concrete in M-25 of trap/ granite/ quartzite/ gneiss metal for R.C.C. beams and lintels as per detailed designs and drawings or as directed including steel centering, formwork, cover blocks, laying/pumping, compaction and roughening the surface if special finish is to be provided and curing etc. complete. (Excluding reinforcement and structural steel).with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)					
	First Floor	1.98	15195.50	Rupees Fifteen Thousand One Hundred Ninety Five & Fifty Paise only.	M3	30026.00

Item No.	Particulars of item	Qty	Rate		Unit	Amount
			In Figures	In Words		
	Third Floor	1.98	15444.55	Rupees Fifteen Thousand Four Hundred Forty Four & Fifty Five Paise only.	M3	30518.00
3	Providing and laying Cast in situ/Ready Mix cement concrete M-25 of trap/ granite / quartzite/ gneiss metal for R.C.C. slabs and landings as per detailed designs and drawings including steel centering, formwork, cover blocks, laying/pumping, compaction finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening if special finish is to be provided and curing etc. complete.(Excluding reinforcement and structural steel).with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)					
	First Floor	3.43	16959.35	Rupees Sixteen Thousand Nine Hundred Fifty Nine & Thirty Five Paise only.	M3	58137.00
	Third Floor	3.43	17241.65	Rupees Seventeen Thousand Two Hundred Forty One & Sixty Five Paise only.	M3	59104.00
4	Providing and laying Cast in situ/Ready Mix cement concrete in M-25 of trap/ granite/ quartzite/ gneiss metal for R.C.C. pardi of required thickness including steel centering, formwork, cover blocks, laying/pumping, compacting and roughening them if special finish is to be provided and curing complete. (Excluding reinforcement and structural steel).with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)					

Item. No.	Particulars of item	Qty	Rate		Unit	Amount
			In Figures	In Words		
	First Floor	2.79	18691.4	Rupees Eighteen Thousand Six Hundred Ninety One & Forty Paise only.	M3	52186.00
	Third Floor	2.79	19006.40	Rupees Nineteen Thousand Six & Forty Paise only.	M3	53066.00
5	Providing and fixing in position TMT - FE - 500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, drawings and schedules. including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete.					
	First Floor	1.34	95250.15	Rupees Ninety Five Thousand Two Hundred Fifty & Fifteen Paise only.	MT	127349.00
	Third Floor	1.34	97044.25	Rupees Ninety Seven Thousand Forty Four & Twenty Five Paise only.	MT	129748.00
6	Providing internal cement plaster 20mm thick in Single coats in cement mortar 1:4 without neeru finish, to concrete, brick surface, in all positions including scaffolding and curing etc. complete.					
	First Floor	55.56	447.15	Rupees Four Hundred Forty Seven & Fifteen Paise only.	M2	24842.00
	Third Floor	55.56	454.80	Rupees Four Hundred Fifty Four & Eighty Paise only.	M2	25267.00

Item No.	Particulars of item	Qty	Rate		Unit	Amount
			In Figures	In Words		
7	Providing internal cement plaster 12mm thick in single coat in cement mortar 1:4 without neeru finish to concrete or brick surfaces, in all positions including scaffolding and curing etc. complete.					
	First Floor	17.06	321.35	Rupees Three Hundred Twenty One & Thirty Five Paise only.	M2	5484.00
	Third Floor	17.06	326.90	Rupees Three Hundred Twenty Six & Ninety Paise only.	M2	5578.00
8	Providing internal cement plaster 6 mm thick in a single coat in cement mortar 1:4 without neeru finish to concrete surface in all positions including scaffolding and curing etc. complete.					
	First Floor	15.74	232.6	Rupees Two Hundred Thirty Two & Sixty Paise only.	M2	3662.00
	Third Floor	15.74	236.65	Rupees Two Hundred Thirty Six & Sixty Five Paise only.	M2	3726.00
9	Providing and applying water proofing treatment using acrylic polymer modified cement based water proofing coating with fibre glass mesh mixing at the rate of powder to liquid (2:1) by weight covering 9 to 10 Square Metre /Kilogram with two coat using approved chemicals for masonry and concrete surface by brush covering 7 years guarantee on Stamp Papers etc. complete.					
	First Floor	32.81	747.15	Rupees Seven Hundred Forty Seven & Fifteen Paise only.	M2	24513.00
	Third Floor	32.81	759.45	Rupees Seven Hundred Fifty Nine & Forty Five Paise only.	M2	24916.00

Item. No.	Particulars of item	Qty	Rate		Unit	Amount	
			In Figures	In Words			
10	Providing and fabricating structural steel work in rolled sections like joists, channels, angles, tees etc. as per detailed design and drawings or as directed including cutting, fabricating, hoisting, erecting, fixing in position making riveted/bolted/welded connections without connecting plates, braces etc. and including one coat of anticorrosive paint and over it two coats of oil painting of approved quality and shade etc. complete.						
	First Floor	0.02	103027.50	Rupees One Lakh Three Thousand Twenty Seven & Forty Five Paise only.	MT	2504.00	
	Third Floor	0.02	105064.30	Rupees One Lakh Five Thousand Sixty Four & Thirty Paise only.	MT	2553.00	
Total cost of work						Rs.	680012.00

Rupees Six Lakhs Eighty Thousand Twelve Only

Note:-

- 1) I/We have ready to execute the work as directed by Engineer/Architect Incharge.
- 2) I/WE agree to carry out the work as per std. PWD specification.
- 3) I/We have personally inspected the site and read/understand all terms and conditions including additional / special condition of removing existing pipeline connection, motor, electric connection for execution of work and redoing the same and testing etc. complete...
- 4) I/We hereby ready to execute the work specified in schedule B at

.....%

ABOVE / BELOW / AT PAR of the schedule of rates .

Contractor


 Civil Engineer
 VANAMATI, Nagpur.